

Dr. Deepak Singh
Officer, In charge R&M



SVP/R.M/2025/ 168
Dated 03.11.2025

Notice

Name of work:- Repair & Maintenance work at Veterinary Pharmacology & Toxicology Lab at Veterinary College. Sealed quotations are invited from the contractors/reputed firms/ government agencies for the maintenance works in the university. The sealed quotations should reach to the **Officer In charge R&M, College of Technology** on or before date: 11/11/2025 at 5.00 PM by speed post/ registered post to the S.V.P.UA&T, Meerut-250110. The details of works are given below:-

S. No.	Particulars of Work	Qty	Rate	Amt
1	P/F vitrified floor tiles in different size (thickness in the specified by manufacture) with wate adjustment less than 0.09 % and in all colors and shade laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Course sand) jointing with grey cement slurry @ 3.3 kg /sqm i/c Grouting the joints with white cement and matching pigment etc complete size: (600 mm x 600 mm)	16.00 Sqm		
2	P/L Reinforced cement concrete 1:1.5:3 01 cement : 1.5 coarse sand zone III Derived from natural sources 3 graded stone aggregate 20 mm nominal size Drived from natural Source.	0.600 Cum		
3	Steel reinforcement for R.C.C work i/c straightening, cutting, bending placing in passion and binding all complete above plinth level thermo mechanically treated bars of grade fe-500D or more.	35.80 Kg		
4	Brick work with common burnt clay F.P.S (non modular) brick of class designation 7.5 in foundation and plinth in cement mortar 1:4(1 cement : 4 coarse sand)	0.414 Cum		
5	12 mm cement Plaster of mixe 1:6 (1 cement: 6 fine sand)	7.20 Sqm		
6	Granite stone one Counter slab jointing over 20 mm average thickness base laid overhand Jointing with grew cement slurry mixed with pigment to match the shade Slab i/c Rubbing and brushing Complete with base of cement mortar 1:4 (1 Cement : Coarse sand) 25 mm thick.	7.20 Sqm		
7	S/F HDMR Wooden cub board 18 mm thick (both side laminated) i/c supply of all Supply of all Materials L.T&P etc. Required for proper Completion of the works.	6.00 Sqm		
8	Distempering with first quality acrylic distemper (ready mixed) having v.o.c (volalite Organic compound) Contract Less than 50 gram/lit of approved brand and manufacture i/c applying additional coat wherever required to achieve even shade and color old work (one or more coat)	64.11 Sqm		
9	Panting with synthetic enamel paint of approved brand and manufacture of required color to give an even shade (one or more coat on old work) As per DSR No- 13.99.1	7.47 Sqm		
10	P/A white cement based putty of average thickness 1 mm of approved brand and manufacture over the plastered and wall surface to prepare the surface even and smooth complete.	12.82 Sqm		
11	12 mm thick cement Plaster finished with a floating coat of neat cement of mix 1:4 (1 cement: 4 fine sand)	8.15 Sqm		
12	P/F white brackets china Laboratory sink size (600 mm x 450 mm 200 mm) with C.I. brackets . C.P brass waste pipe and rubber plug, 40 mm c.p brass trap with necessary C.P brass unions complete i/c painting of fitting and bracket s, cutting and making good the wall wherever required.	On Job		
Total				
G.S.T. as per Government Rule				
Grand Total				

Terms & Conditions

- The name of work should be mentioned on the envelope.
- The G.S.T or any other charges over and above the rates should be mentioned clearly.
- The envelope should be sealed and super scribed quotation for repair work.
- The payment will be made through E- mode only after the work satisfactory completed. The details of the banks account, IFSC code etc. should be mentioned.
- The Hon'ble Vice-Chancellor, S.V.P.U.A&T, Meerut reserved the right to accept or reject any or all the quotations without assigning and reasons thereof.
- Copy of pan card should be enclosed .
- Copy of G.S.T. registration should be enclosed .
- Quotation received after due date will not be entertained.

Deepak Singh
03.11.2025
(Officer, In charge R&M)

Copy to :-

- All notice board .
- The Chairman / all Committee Members .
- The Comptroller for kind information.
- The Officer In charge (IT) with the request to upload the notice on university website.
- P.R.O. to Hon'ble Vice-Chancellor for kind information.

(Officer, In charge R&M)

Sardar Vallabhbhai Patel University of Agriculture and Technology, Meerut - 250110

Dr. Deepak Singh
Officer, In charge R&M



SVP/R.M/2025/167
Dated: 03.11.2025

Notice

Name of work:- Repair & Maintenance Civil Work at Tagore & Vivekananda Hostels. Sealed quotations are invited from the contractors/reputed firms/ government agencies for the maintenance works in the university. The sealed quotations should reach to the Officer, In charge R&M, College of Technology on or before date: 10.11.2025 at 5.00 PM by speed post/ registered post to the S.V.P.UA&T, Meerut-250110. The details of works are given below:-

S. No.	Particulars of Work	Qty	Rate	Amount
1	Providing & fixing Rectified glazed floor tiles of size (300 x 300 mm) (thickness to be specified by the manufacturer) of 1 st quality conforming to IS : 15622 of approved make in all colour shades except white ivory grey fume red brown Laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/Sqm including pointing the joints with white cement and Matching pigment etc. complete.	14.32 Sqm		
2	P/L in cement concrete 1:4 (1 cement: 4 Coarse sand) 8 Stone Aggregate 40 mm nominal size) and curing of concrete, i/c cost of form work in foundation and floors.	1.07 Cum		
3	P/F M.S Tubular frames for doors. Windows, ventilators and cupboard with rectangular/L-Type sections made of 1.60 mm thick M.S Sheet, joints mitred, welded and grinded finish. With profiles of required size, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer. Fixing with 15 x 3 mm Lugs 10 cm long embedded in cement concrete block 15x10x10 cm of c.c. 1:3:6 (1 cement 3 Coarse sand : 6 Graded stone aggregate 20 mm nominal size)	374.40 Kg		
4	Supply C.I. L- Drop 200 mm	12 No.		
Total				
GST as per Government Rule				
Grand Total				

Terms & Conditions

- The name of work should be mentioned on the envelope.
- The G.S.T or any other charges over and above the rates should be mentioned clearly.
- The envelope should be sealed and super scribed quotation for repair work.
- The payment will be made through E- mode only after the work satisfactory completed. The details of the banks account, IFSC code etc. should be mentioned.
- The Hon'ble Vice-Chancellor, S.V.P.U.A&T, Meerut reserved the right to accept or reject any or all the quotations without assigning and reasons thereof.
- Copy of pan card should be enclosed.
- Copy of G.S.T. registration should be enclosed.
- Quotation received after due date will not be entertained.

Deepak Singh
03.11.2025
(Officer, In charge R&M)

Copy to :-

- All notice board .
- The Chairman / all Committee Members.
- The Comptroller for kind information.
- The Officer In charge (IT) with the request to upload the notice on university website.
- P.R.O. to Hon'ble Vice-Chancellor for kind information.

(Officer, In charge R&M)

Sardar Vallabhbhai Patel University of Agriculture and Technology, Meerut - 250110

Dr. Deepak Singh
Officer, In charge R&M



SVP/R.M/2025/ 157
Dated 30.10.2025

Notice

Name of work:- Repair & Maintenance at Department of Veterinary Physiology and Biochemistry at College of Veterinary in S.V.P Agri. University Meerut. Sealed quotations are invited from the contractors/reputed firms/ government agencies for the maintenance works in the university. The sealed quotations should reach to the Officer, In charge R&M, College of Technology on or before date: 10.11.25 at 5.00 PM by speed post/ registered post to the S.V.P.UA&T, Meerut-250110. The details of works are given below:-

S. No.	Particulars of Work	Qty	Rate	Amount
1	P/L Reinforced cement concrete work in wall (any Thickness) i/c attached Plasterad Buttresses Plinth and Strings courses fillets Column Pillars, Piers, abutment post and struts etc above plinth level upto floor five level excluding cost of shuttering centering finishing and enforcement. (a) 1:1.5:3 01 cement : 1.5 coarse sand zone III Derived from natural sources 3 graded stone aggregate 20 mm nominal size Derived from natural Source.	2.70 Cum		
2	12 mm thick cement Plaster finished with a floating coat of neat cement of mix 1:6 (1 cement: 6 fine sand)	54.00 Sqm		
3	Steel reinforcement for R.C.C work i/c straightening, cutting, bending placing in passion and binding all complete above plinth level thermo mechanically treated bars of grade fe-500D or more.	2.56 Qtl		
4	Brick work with common burnt clay F.P.S (non modular) brick of class designation 7.5 in foundation and plinth in cement mortar 1:4(1 cement : 4 coarse sand)	1.72 Cum		
5	Supply and fixing lab sink with all fixture fitting Complete.	05 Job		
6	Supply and fixing 16 A switch and Socket with required all Accessories (Cable+Gang Box+Battern) Required proper Completion of the works.	08 Job		
Total				
GST as per Government Rule				
Grand Total				

Terms & Conditions

- The name of work should be mentioned on the envelope.
- The G.S.T or any other charges over and above the rates should be mentioned clearly.
- The envelope should be sealed and super scribed quotation for repair work.
- The payment will be made through E- mode only after the work satisfactory completed. The details of the banks account, IFSC code etc. should be mentioned.
- The Hon'ble Vice-Chancellor, S.V.P.U.A&T, Meerut reserved the right to accept or reject any or all the quotations without assigning and reasons thereof.
- Copy of pan card should be enclosed .
- Copy of G.S.T. registration should be enclosed .
- Quotation received after due date will not be entertained.

Deepak Singh
30.10.2025
(Officer, In charge R&M)

Copy to :-

- All notice board .
- The Chairman / all Committee Members .
- The Comptroller for kind information.
- The Officer In charge (IT) with the request to upload the notice on university website.
- P.R.O. to Hon'ble Vice-Chancellor for kind information.

(Officer, In charge R&M)

Sardar Vallabhbhai Patel University of Agriculture and Technology, Meerut - 250110

Dr. Deepak Singh
Officer, In charge R&M



SVP/R.M/2025/160
Dated 30.10.2025

Notice

Name of work:- Repair & Maintenance at State Bank of India at College of Agriculture in S.V.P Agri. University Meerut. Sealed quotations are invited from the contractors/reputed firms/ government agencies for the maintenance works in the university. The sealed quotations should reach to the Officer, In charge R&M, College of Technology on or before date: **11.11.25** at 5.00 PM by speed post/ registered post to the S.V.P.UA&T, Meerut-250110. The details of works are given below:-

S. No.	Particulars of Work	Qty	Rate	Amount
1	Dismantling brick work manually/by mechanical means including stacking of serviceable material within 50 metres lead. As per direction of Engineer-in charge.	0.217 CUM		
2	First Class Brick work 1:4 cement: 4 Coarse sand Mortar in super structure for 230 mm thick wall.	0.966 CUM		
3	12 mm thick cement Plaster finished with a floating coat of neat cement of mix 1:4 (1 cement: 4 fine sand)	17.68 Sqm		
4	Providing & fixing Rectified glazed floor tiles of size (300 x 300 mm) (thickness to be specified by the manufacturer) of 1 st quality conforming to IS : 15622 of approved make in all colour shades except white ivory grey fume red brown Laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/Sqm including pointing the joints with white cement and Matching pigment etc. complete.	17.68 Sqm		
5	Steel work built up tubular (round, square or rectangular hollow tubes etc) including cutting, hoisting fixing in position and applying a priming coat of approved steel primer i/c welding and bolted with special shaped washers etc complete. Hot finished welded type tubes	33.50 Kg		
6	Supply and fixing Becolite Flush Floor shutter 12 mm thick supply of all materials L.T&P. etc. Required for proper Completion of the works.	1.89 Sqm		
7	Supply and fixing CPVC pipe 20 mm dia.	3.00 Mtr		
8	Supply and fixing Flexible PVC waste pipe 40 mm dia.	01 No.		
9	P/F C.P brass Angle valve.	01 No.		
10	P/F Unplastased PVC Connection pipe with brass Union 15 mm Nominal Bore dia.	01 No.		
11	Supply and fixing CPVC pipe 20 mm dia.	3.00 Mtr		
Total				
GST as per Government Rule				
Grand Total				

Terms & Conditions

- The name of work should be mentioned on the envelope.
- The G.S.T or any other charges over and above the rates should be mentioned clearly.
- The envelope should be sealed and super scribed quotation for repair work.
- The payment will be made through E- mode only after the work satisfactory completed. The details of the banks account, IFSC code etc. should be mentioned.
- The Hon'ble Vice-Chancellor, S.V.P.U.A&T, Meerut reserved the right to accept or reject any or all the quotations without assigning and reasons thereof.
- Copy of pan card should be enclosed .
- Copy of G.S.T. registration should be enclosed .
- Quotation received after due date will not be entertained.

Deepak Singh
30.10.2025
(Officer, In charge R&M)

Copy to :-

- All notice board.
- The Chairman / all Committee Members .
- The Comptroller for kind information.
- The Officer In charge (IT) with the request to upload the notice on university website.
- P.R.O. to Hon'ble Vice-Chancellor for kind information.

(Officer, In charge R&M)

Sardar Vallabhbhai Patel University of Agriculture and Technology, Meerut - 250110

Er. Sanjay Kumar Gupta
In charge Construction



SVP/R.M/2025/ 154

Dated 27.10.2025

Notice

Name of work:- Reapir& Maintenance Remaking of the university name board at main gate no. 01, Sealed quotations are invited from the contractors/reputed firms/ government agencies for the maintenance works in this regard. The sealed quotations should reach to the Officer, In charge R&M, College of Technology on or before date: 4.11.2025 at 5.00 PM by speed post/ registered post to the S.V.P.UA&T, Meerut-250110. The details of works are given below:-

S.No	Particulars of Work	Qty	Rate	Amount
1	Remaking of the university name board at main gate no. 01 by using old and new materials wherever required after repairing and butting S.S. letters and words supply of required materials labour, tools & plan etc required for proper completion of the work. (Both sides)	One Job		
Total				
GST as per Government Rule				
Grand Total				

Terms & Conditions

- The G.S.T or any other charges over and above the rates should be mentioned clearly.
- The envelope should be sealed and super scribed quotation for repair work.
- The payment will be made through E- mode only after the work satisfactory completed. The details of the banks account, IFSC code etc. should be mentioned.
- The Hon'ble Vice-Chancellor, S.V.P.U.A&T, Meerut reserved the right to accept or reject any or all the quotations without assigning and reasons thereof.
- Copy of pan card should be enclosed .
- Copy of G.S.T. registration should be enclosed .
- Quotation received after due date will not be entertained.

G 27.10.2025
(In charge Construction)

Copy to :-

- All notice board .
- The Chairman / all Committee Members .
- The Comptroller for kind information.
- The Officer In charge (IT) with the request to upload the notice on university website.
- P.R.O. to Hon'ble Vice-Chancellor for kind information.

G 27.10.2025
(In charge Construction)